

Nuclear News Presents: **A Look Back at the Fukushima Daiichi Accident** Tuesday, March 2



Webinar Program

- Report Safety Recommendations
 - Dale Klein, Former Chairman of USNRC
 - Mike Corradini, Emeritus Professor, University of Wisconsin
- Lessons Learned from Forensics
 - Joy Rempe, Principal, Rempe and Assoc. LLC
- Site Cleanup & Decommissioning
 - Lake Barrett, Senior advisor, TEPCO and IRID
- Socio-Economic Aspects
 - Paul Dickman, Senior Policy Fellow, Argonne National Lab

ANS Special Committee on Fukushima

The special committee was formed by ANS in Spring 2011.

The objective was to provide a clear and concise explanation of the events surrounding the accident to the general public as well as the needed actions to better communicate with the public.

http://fukushima.ans.org

Co-Chairs: Dale Klein, Univ. of Texas, Michael Corradini, Univ. of Wisconsin Paul T. Dickman, Argonne National Laboratory Jacopo Buongiorno, Massachusetts Institute of Technology Hisashi Ninokata, Tokyo Institute of Technology Mike Ryan, M.T. Ryan and Associates LLC Craig D. Sawyer, Retired Senior Engineer Amir Shahkarami, Exelon Nuclear Akira Tokuhiro, University of Idaho

Special Thanks to Laura Scheele, Former ANS Staff (now at INL)

ANS Special Committee on Fukushima

SUBCOMMITTEE VOLUNTEER CONTRIBUTORS

Accident Cleanup & Waste Management

Adam H. Levin William R. Nelson Wayne Johnson

Accident Sequence Analysis

David H. Johnson Bal-Raj Sehgal Paul Sicard Christophe Journeau

Health Physics & Radiation Biology

Wade Allison Bryan P. Bednarz Peter F. Caracappa Stephen V. Musolino Kathy D. Weaver

Regulatory Issues

Mario Fontana David H. Johnson Kevin Lynn John Madell Arthur T. Motta Bal-Raj Sehgal


Risk Communication

Edward M. Davis Margaret Harding W. David Pointer Daniel Yurman

Fukushima-1 Accident Summary

- March 11th earthquake/tsunami struck Fukushima Daiichi, a six-unit BWR nuclear plant site on the NE coast of Japan
- Earthquake/tsunami caused station blackout, disabling safety systems
- Extensive fuel damage occurred in the reactors at Units 1-3
- Containment failure at Units 1-3 resulted in a release of radioactive materials into atmosphere and ocean
- The accident resulted in large environmental impacts
- Nuclear Industry and Regulators have learned lessons from the events and the analysis

Tsunami Effect on Power Plant Sites



Report Safety Recommendations

Report focus on key technical issues as a basis for regulatory actions

- Risk-informed approach to safety; e.g., SFP study, SAWA study
- External Hazards: Confirm plants have consistent and appropriate design bases for natural disasters (reassess on periodic basis)
- Multi-unit risk should be part of plant safety assessments
- Accident diagnostic tool development; BWROG, PWROG efforts
- Plant hardware design modifications; e.g., FLEX approach (use of installed safety systems, on-site operator actions, off-site assist)
 - Protect DC batteries and improve robustness of RCIC & AFW
 - Ability to reroute water sources with robust pump systems
 - Logistically position fuel, generators and pumps to move onto plant site

Report Safety Recommendations

- Develop Severe Accident Guidelines (coordination with Emergency Proc. by BWR & PWR Owner's groups)
- Command & control: Confirm that command/control of an accident resides with plant manager on-site to assure safety during any event
- Emergency Planning: Confirm that current approach to EP is appropriate
- Health Physics assessment need to continue for long-term (e.g., https://www.mdpi.com/1660-4601/15/6/1219)
- Perform Societal Risk comparison for all energy sources.

Interim Lessons from Daiichi Forensics Examinations

Joy Rempe Rempe and Associates, LLC

Acknowledgement:

This presentation draws upon information from the DOE-sponsored U.S. Forensics Effort, a collaborative U.S. /Japan effort with participation by experts in plant operations and reactor safety. In particular, the author would like to acknowledge the contributions of Shinya Mizokami and Tatsuro Kobayashi, TEPCO Holdings Company; Akira Nakayoshi and Tadahiro Washiya, Japan Atomic Energy Agency; Masaya Yasui, Japan Nuclear Regulatory Authority; Phil Amway, Exelon Corporation and BWR Owners Group (BWROG); Mitch Farmer, Argonne National Laboratory; Bill Williamson, TVA and BWROG; Kevin Robb, Oak Ridge National Laboratory; Jeff Gabor, Jensen Hughes; Wison Luangdilok, Chan Paik, and Marty Plys, Fauske and Associates, LLC; Randy Bunt, Southern Nuclear Company and BWROG; Phil Ellison, GE Hitachi and BWROG; Roy Linthicum, PWR Owners Group (PWROG); Lucas Albright, Nathan Andrews, Randy Gauntt (retired), and David Luxat, Sandia National Laboratories; Michael Corradini, University of Wisconsin-Madison; Karen Kirkland, Texas A&M University, Kelli Voelsing and Matthew Nudi, Electric Power Research Institute; Donald Algama, Hossein Esmaili, Richard Lee (retired) and Don Marksberry, US Nuclear Regulatory Commission; and Damian Peko, US Department of Energy.

Interim Lessons from Daiichi Forensics Examinations

Joy Rempe Rempe and Associates, LLC

Acknowledgement:

This presentation draws upon information from the DOE-sponsored U.S. Forensics Effort, a collaborative U.S. /Japan effort with participation by experts in plant operations and reactor safety. In particular, the author would like to acknowledge the contributions of Shinya Mizokami and Tatsuro Kobayashi, TEPCO Holdings Company; Akira Nakayoshi and Tadahiro Washiya, Japan Atomic Energy Agency; Masaya Yasui, Japan Nuclear Regulatory Authority; Phil Amway, Exelon Corporation and BWR Owners Group (BWROG); Mitch Farmer, Argonne National Laboratory; Bill Williamson, TVA and BWROG; Kevin Robb, Oak Ridge National Laboratory; Jeff Gabor, Jensen Hughes; Wison Luangdilok, Chan Paik, and Marty Plys, Fauske and Associates, LLC; Randy Bunt, Southern Nuclear Company and BWROG; Phil Ellison, GE Hitachi and BWROG; Roy Linthicum, PWR Owners Group (PWROG); Lucas Albright, Nathan Andrews, Randy Gauntt (retired), and David Luxat, Sandia National Laboratories; Michael Corradini, University of Wisconsin-Madison; Karen Kirkland, Texas A&M University, Kelli Voelsing and Matthew Nudi, Electric Power Research Institute; Donald Algama, Hossein Esmaili, Richard Lee (retired) and Don Marksberry, US Nuclear Regulatory Commission; and Damian Peko, US Department of Energy.

Nuclear News

Working together to enhance

uclear reactor safety 3

DOE Forensics Effort Coordinated with TEPCO D&D Activities

Objectives:

- Develop consensus US input for high priority time-sequenced examination tasks and supporting research that can be completed with minimal disruption of TEPCO Decommissioning and Decontamination (D&D) activities
- Evaluate obtained information to:
 - Gain a better understanding of events that occurred in each unit at Daiichi
 - Gain insights to reduce uncertainties in predicting phenomena and equipment performance during severe accidents
 - Provide insights beneficial to TEPCO Phase 2 Fuel Debris Retrieval Evaluations
 - Confirm/improve guidance for severe accident prevention, mitigation, and emergency planning
 - Periodically update/refine original information requests
- Facilitate implementation of Japan-led international research efforts to support D&D

Motivations:


- Provides US access to full-scale, prototypic data from multiple units with distinct accident signatures
- Provides Japan access to US expertise in plant operations, severe accident modeling & testing, and defueling & cleanup

FY2020 report publicly available (<u>https://www.osti.gov/biblio/1602189</u>)






Similar Approach Applied for Post-Accident Investigations



- Process relies on instrumentation data, post-accident examinations, existing severe accident knowledge, and engineering analyses
- Efforts initially focused on stabilizing reactors and associated structures before focusing on cleanup
- Key to prioritize activities, emphasizing those that:
 - Minimize future radiation releases and site hazards,
 - Ensure safe and efficient D&D, and
 - As resources allow, reduce uncertainties related to accident progression and reactor safety enhancement.
- Most high priority information <u>desired</u> for reactor safety insights <u>required</u> for D&D

1F1 Information Confirms Adequacy of Revised U.S. Severe Accident Management Strategies






Graphics Courtesy of TEPCO and Fukushima Central Television (FCT)


- BWR/3 rated at 460 MWe in Mark I containment with Isolation Condensers (ICs) for decay heat removal
- Seismic accelerations, tsunami flooding, and station blackout hindered accident mitigation:
 - IC operation
 - Instrumentation availability and calibration
 - Venting
- Plant data, radiation surveys, calculations, and images from muon tomography and robotic inspections indicate:
 - Significant fuel heatup and relocation
 - High temperatures/pressures led to Primary Containment Vessel (PCV) leakage, hydrogen release, and combustion
 - Significant damage to the reactor building and missile shield
 - Reactor Pressure Vessel (RPV) failure and significant relocation to PCV (initial examinations limited to locations external to pedestal)
 - Extent of core concrete interaction uncertain

1F2 Information Confirms Adequacy of Revised U.S. Severe Accident Management Strategies




- BWR/4 rated at 784 MWe in Mark I containment with Reactor Core Isolation Cooling (RCIC) system for decay heat removal
- Available information indicates accident progression less advanced:
 - RCIC operation continued for nearly 3 days.
 - H₂ explosion precluded due to "unintentional" early Reactor Building (RB) venting
 - RPV failure with ex-vessel debris holdup on structures
 - Significant relocation and spreading into PCV
 - PCV water level lower than in Unit 1
 - Units 1 and 3 explosions delayed recovery efforts

1F3 Information Confirms Adequacy of Revised U.S. Severe Accident Management Strategies



Graphics Courtesy of TEPCO, IRID, and FCT



- BWR/4 rated at 784 MWe in Mark I containment with RCIC system.
- Available information indicates accident progression more advanced than in Unit 2:
 - RCIC operation continued for less than 1 day
 - Significant fuel heatup and relocation
 - High temperatures/pressures led to PCV leakage and a multi-stage explosion
 - Venting through Standby Gas Treatment System led to Unit 4 explosion
 - RPV failure with significant relocation and spreading into PCV
 - PCV water level much higher than in Units 1 and 2

Daiichi-Ten Years of Decontamination and Decommissioning



Three Mile Island 1984 American Nuclear Society Webinar March 2, 2021 Lake H. Barrett

Lake@Lbarrett.com

Photos Courtesy of TEPCO



Fukushima Daiichi 2015

March Nuclear News ans.org/nn

FUKUSHIMA DAIICHI 10 YEARS ON

By Lake Barrett

t was a rather normal day back on March 11, 2011, at the Fukushima Daiichi nuclear plant before 2:45 p.m. That was the time when the Great Tohoku earthquake struck, followed by a massive tsunami that caused three reactor meltdowns and forever changed the nuclear power industry in Japan and worldwide. Now, 10 years later, much has been learned and done to improve nuclear safety, and despite many challenges, significant progress is being made to decontaminate and defuel the extensively damaged Fukushima Daiichi reactor site. This is a summary of what happened, progress to date, current situation, and the outlook for the future there.

L. Barrett Consulting LLC

March 2011 Units 1-4 Major Damage & Contamination



March 2011 Starting Conditions

- Reactor Buildings Heavy Damage & High Radiation
- Melted Cores on Floor With Leaking Primary Containments
- Four Steaming Filled Spent Fuel Pools in Damaged Buildings
- Highly Contaminated Site
- Cs Dust Airborne Releases
- Hundreds of Tons per day of Highly Radioactive Water Leaking Into Basements and Pipe Trenches to Sea

D&D General Approach

- Forward With Risk Informed Risk Reduction
- Worker Safety & Improve Working Conditions
- Stabilize Core Debris
- Control & Minimize Airborne Releases
- Control, Decontaminate, Store, and Eventually Safely Dispose of Radioactive Waters
- Defuel Four Damaged Spent Fuel Pools
- Decontaminate Site and Buildings
- Characterize Internal Core Debris Conditions
- Remove Core Debris
- Safely Process and Store Radioactive Wastes

Airborne Mitigation



Dust Suppression Resin Application



Unit 1 Fabric Enclosure 55M High & 47M X 42M

Extensive Soil Paving

Water Release Mitigation Contain/Retard Intake Structure Cs/Sr Contamination



Sluice Gate to Minimize Outflow To Ocean



Sealing Underground Trenches



Steel Seawall Construction

L. Barrett Consulting LLC



Silt Fences, To Adsorb Cs/Sr



Ice wall Construction

Water Retention Tank Farms

Quickly Constructed & Expanded with Welded Tanks









L. Barrett Consulting LLC

Water Decontamination Systems Cs & Contaminate Removal Allowed Recycle Cooling



Individual Zeolite Beds



Shielded Skids

Advanced Liquid Processing System: Removes Most But Tritium

Operational 2013



High Radiation Solid Waste Storage



and the second s	Service and a service of the service	the states
		1
		- Common
		July 1
11/1/1/1	1 1 1 1 1 1	
		Sec. 1
	3 3 3 3	
Commenter and	I HAR I	
	and any second second second second second	
In the second second second second		
failed and the same for some for some for some		
	and the second s	-11/
		. = 11.
	Annes Annes Annes Anne	in a contract of

New Canister Storage Facility


5,000+ Cans March 2021 1-3M high each Highly Radioactive ~Sv+/Hr.

L. Barrett Consulting LLC

Processed Salt Water Containing Tritium Is Stored On Site ~1,000+ Tanks & ~1 Million Tons



Mitigating Groundwater Paths To Sea Minor Contamination Major Public Concern



Spent Fuel Pool Defueling- Unit 4

Explosion Caused By Unit 3 H2 Backflow-Not SFP





2011

2013-New Seismic Cantilevered Building

Unit 4 SFP Defueling Success








All 1533 Assemblies Safely Removed in 2014

L. Barrett Consulting LLC





Spent Fuel Pool Defueling-Unit 3





2011-With Steaming Spent Fuel Pool

2018-New Seismic Defueling Building

Unit 3 SFP Robotic Defueling: Completed








All 566 Fuel Assemblies Safely Removed 28 February 2021

Spent Fuel Pool Defueling- Unit 2





Defueling Floor Access-2018



New Defueling Building Plan 2024-26

2011

Spent Fuel Pool Defueling- Unit 1




2011



2013-Dust Mitigation Cover

Fuel-handling facility



Rubble removal (image)

Fuel removal (image)

New Defueling Building Plan for 2027-28

Robotic Internal PCV Investigations



Unit 1 Torus Boat



U2 Torus Magnetic Crawler



Unit 2 Swimming Robot





U1 Shape Changing





U2 Scorpion

U3 Sunfish


Unit 2 Core Debris Investigations



Fuel Assembly Lifting Handle & Ejected Core Internals


L. Barrett Consulting LLC

Unit 2- Under Pedestal Core Debris



Under Reactor Vessel: Melted Steel Grating

Unit 2 Core Debris Sample Removal



L. Barrett Consulting LLC

22 M Long Remote Arm

*It can be alternatively replaced a tool.

Mounted sensor at the tip of the arm

Decontamination Robots Supports Defueling Access





Dry Ice Surface Blaster/Vacuum Robot System

Debris Removal Robot

Offsite Decontamination Mostly Complete



House Roofs



School Buildings



Parking Lots



L. Barrett Consulting LLC

Children's Playgrounds

Offsite Decontamination Waste Management



Planning For a ~ 20 Million+ M3 Interim Storage Facility **Currently Thousands of Local Storage Sites**

Difficult Social Issues

Human Feelings & Reactions



L. Barrett Consulting LL

Future Outlook

- Much Has Been Technically Accomplished & Many Challenges Ahead
- Social/Political Considerations Are Significant
- USA Successfully Recovered from the Three Mile Island Accident and Learned with Improved Nuclear Safety and Reactor Performance
- Japan Has the Capacity to Do So Also

Fukushima: Social and Economic Impacts and Recovery

American Nuclear Society Webinar March 2, 2021 Paul Dickman


Argonne National Laboratory

Photo credit: Asahi Shimbun and REUTER

Quick Disclaimer

- I serve as an International Special Advisor to the Nuclear Damage Compensation and Decommissioning Facilitation Corporation (NDF), the Japanese Government agency responsible for the decommissioning of the Fukushima Daiichi accident site.
- My views are in support of the American Nuclear Society and may not reflect those of Argonne National Laboratory or the NDF.
- Contact: <u>Paul.Dickman@anl.gov</u>

The Great East Japan Earthquake and Tsunami Forced Massive Regional Evacuation



Human Casualties

- Deceased: 19,729
- Missing: 2,559
- Injured: 6,233


Damaged Buildings

- Completely destroyed: 121,996
- Half destroyed: 282,941
- Partially Destroyed: 748,461

Fukushima Area Devastation: Triple Impact

Damage status [As of 2020.7.6]

Totally destroyed: 15,435 houses
 Half destroyed: 82,783 houses







Ten Years Later: Thousands Remain Displaced

- A total of 164,865 residents of the Fukushima Prefecture were forced into evacuating their homes.
- Approximately 38 thousand are still under evacuation orders but many thousands of evacuees will never return.
- Some townships have less than 35% returnees.

Transition of evacuees:




"Difficult to Return" Zones Remain Hindrance to Revitalization




acsurao ha	Designate Special Zones for Reconstruction and		
la		Revitalization	
		Sep 15 2017]	
5ha	Okuma Town [Nov 10 2017]	
	Namie Town [Dec 22 2017]	
OWD	Tomioka Town [Mar 9 2018]	
	litate Village [Apr 20 2018]	
n ve d for ation	Katsurao Village [May 11 2018]	
on m	Difficult-to-retu	Annual integrated doses are over 50mSv. Entry is prohibited with some exceptions.	
	zone	 Lodging is prohibited. 	
a , , , , , , , , , , , , , ,	Areas where evacu have been lifted.	and Revitalization	

Food Safety Measures Have Benefited Economic Revival




Transparent Monitoring of Radioactive Materials in Foods



Marine Fisheries Remain Severely Impacted

The Fukushima Region was prized across Japan for its high-quality seafood.



Treated Water Release: An International Mis-Information Campaign

IAGES

Fukushima water release could change human DNA, Greenpeace warns

By Amy Woodyatt and Yoko Wakatsuki, CNN

Updated 10:21 AM ET, Sat October 24, 2020

NAMES OF A DESCRIPTION OF			
Vorld	• LI	• LIVE TV	
	GLOBAL TIMES		
	World worries about release of Fukushima nuclear water		
	By Xu Keyue Source: Global Times Published: 2020/10/18 21:33:40		

ENVIRONMENT Fukushima: How the ocean became a dumping ground for radioactive waste

Taiwan Votes to Maintain Import Ban on Fukushima Food Imports

Seoul mulls response to Fukushima water release 2020-10-20 15:32



Information about Current Progress

Fukushima Prefectural Government Web Site

https://www.pref.fukushima.lg.jp/site/portal-english/

Ministry of Economy, Trade, and Industry (METI)

https://www.meti.go.jp/english/earthquake/nuclear/decommissioning/index.html

Nuclear Damage Compensation and Decommissioning Facilitation Corporation (NDF)

http://www.dd.ndf.go.jp/eindex.html

Ministry of Health, Labor and Welfare

https://www.mhlw.go.jp/english/topics/2011eq/index.html

Tokyo Electric Power Company (TEPCo)

https://www.tepco.co.jp/en/hd/decommission/index-e.html

Summary

- The impact of the Great East Japan Earthquake and Tsunami is generational, recovery will take decades.
- The accident at Fukushima Daiichi NPP overshadows the massive regional destruction.
- Significant progress has been made in regional economic recovery with important exceptions.
- The NDF, METI, and TEPCO are starting to leverage remediation expenditure in supporting economic revitalization.
- Release of treated water from 1F has become a surrogate for international grievances and trade disputes.

The Great East Japan Earthquake and Nuclear Disaster Memorial Museum – Futaba Town



Summer Olympics- 2020 2021

• 2020 Summer Olympics will begin on Friday, July 23, 2021 and ends on Sunday, August 8, 2021

• Japan has made major effort to highlight food and products from Fukushima area as part of Olympics venue and training.

• In Fukushima, the J-Village National Training Center served as central command post for 1F accident. It is again the Olympic training center for soccer.



